
NAMIBIAN PORTS AUTHORITY










Port of Walvis Bay has 3 sections









PORT OF WALVIS BAY - SECTION 1

Port of Walvis Bay: existing commercial port facilities:

- 150 hectares of land area;
- 2. 8 commercial berths;
- 3. 1 x link span ro-ro berth;
- 4. 1 x small craft harbour;
- 5. 1 x 45,000dwt Tanker berth @ -10.4m CD water depth;
- 6. 1 x 2000ton Syncrolift dry docking facility;
- 7. 3 x floating dry docks, max 15000ton capacity;
- 8. 1700m of total berth space;
- 9. Berths 1 to 3 (container berths) = -14.0m CD water depth;
- 10. Berths 4 to 8 (multipurpose berths) = -10.6m CD water depth;




PORT OF WALVIS BAY - SECTION 1

Port of Walvis Bay: Major facilities currently under construction (2014 to 2017):

- 1 x 600m long 8000 TEU container berths @ 16.0m CD water depth;
- 40 hectares of land reclamation for a new container terminal;
- 3. 1 x 300m LOA passenger liner berth @ -11m CD water depth;
- 4. 120m small craft jetty



Port of Walvis Bay – Existing and future layout










Port of Walvis Bay - Section 3 - SADC Gateway





PORT OF WALVIS BAY - SECTION 3 - SADC Gateway

Port of Walvis Bay: SADC GATEWAY future:

- 1330 hectares of land;
- Bulk cargo handling port;
- 3. More than 20 different phases planned;
- 4. Will cater for port growth for the next 50 or more years;
- 5. Focused at SADC and not just Namibia;



Port of Walvis Bay - Section 3 - SADC Gateway

1. Phase 1: Liquid Bulk Terminal for hydrocarbons


- Entrance channel and turning basin to new port;
- 2 x 60,000dwt tanker berths;
- Access trestle;
- Product pipelines;
- Etc.

Phase 1 is being implemented by the Ministry of Mines and Energy, and has commenced on 30 March 2015, for commissioning by 2017.

- 2. Phase 2: LNG Terminal for new power plant
 - Currently on hold
- 3. Phase 3: Multipurpose bulk terminal (<10 million Tons p/a)
 - Feasibility study will commence in 2016;
 - Implementation could start 2017;
 - Commissioning expected by 2019/20



Port of Walvis Bay – Section 3 - SADC Gateway





Port of Walvis Bay - Section 3 - SADC Gateway

LAND FILLING next to the B2 Road

- Namport requested the Contractor building the oil Terminal to use some of the dredged material to do land filling and flatten the dunes on the SADC Gateway port land;
- 2. The land filling will result in a flat surface on which we can then start developing for port operations;

Port of Walvis Bay SADC Gateway - Phase 1 OIL TERMINAL





PROJECT FOCUS

OPORT OF WALVIS BAY NEW CONTAINER
TERMINAL ON RECLAIMED LAND




1. New Container Terminal on Reclaimed Land

Brief description of the project:

- Commenced in May 2014
- Project contains more than 20 contracts;
- EPC Contractor: China Harbour Engineering Company (CHEC);
- Completion date = 2018;



STATUS AS AT SEPTEMBER 2014



STATUS AS AT DECEMBER 2014



STATUS AS AT FEBRUARY 2015



STATUS AS AT APRIL 2015



STATUS AS AT MAY 2015



STATUS AS AT AUG 2015



STATUS AS AT MARCH 2016



New Walvis Bay Container Terminal





New Container Terminal on Reclaimed Land

OVERALL PROJECT PROGRESS TO DATE:

50%

On schedule to commission by 2018



CAPITAL PROJECTS UPDATE

Port of Walvis Bay Waterfront and Marina Development:

1. Ground breaking by 2018;



Waterfrom Development
NAMPORT
Friday, February 13, 28 16

MACKINTOSH LAUTENBACH



Waterfrom Development
NAMPORT
Friday, February 13, 28 16



